




# **SLAG TREATMENT** - **Injection via Furnace Roof**

## **Basic Layout:**

The Lime will be injected via the furnace roof directly into the Delta between the electrodes.







Certified: DIN EN ISO 9001:2000



# **SLAG TREATMENT** - Injection via Furnace Roof

### **PROCESS PARAMETER:**

Pipe / Hose diameter: 3"

Flowrate: up to 500 kg/min

Lime: Lump Lime (CaO content > 90%)

Grain size: 6 - 15 mm, max. 18mm

Bulk Density: ~ 1,0 t/m<sup>3</sup>

Media: <u>Dry</u> Air / N<sub>2</sub>, depending availability

Pressure: 6 bar constant

Media consumption: depending on flow rate

### **ADVANTAGES AND DISADVANTAGES:**

#### Pros:

- Very high flow rate possible
- Early injection in melting cycle
- Injection into the furnace hottest area (Delta between electrodes)
- Fast melt down of Lime due to portion wise injection
- Fast roof exchange due to installation of spare roof

#### Cons:

- Lime fines will be exhausted into Back-house
- Roof / Spare roof installation necessary
- Purge media required
- -Modification of roof panel necessary

Certified: DIN EN ISO 9001:2000